1	Description of Item	Unit	Qty	Rate in	
				Figures	Words
	2	3	4	5	6
146	Providing and laying heavy duty cobble stones 75mm thick inter lock pavers, using cement and course sand for manufacture of block of approved size, shape and colur with a minimum compressive strength of 281 Kg per Sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in betwen joints, final compaction of paver surface joints its final level, including cost of materials, labour and HOM of machineries complete as per specification.	Sqm	50.00	1204.00	Rupees One Thousand Two Hundred Four Only
147	Providing and laying Cinder concrete in cement 1:15 (1 cement: 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications - First Floor	Cum	7.50	2361.00	Rupees Two Thousand Three Hundred Sixty One Only
	Above 125%	Sqm	4.50	2476.71	Rupees Two Thousand Four Hundred Seventy Six and Seventy One Paise Only
148	Providing and laying Cinder concrete in cement 1:15 (1 cement: 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications - Second Floor	Cum	6.00	2361.00	Rupees Two Thousand Three Hundred Sixty One Only
149	Providing and laying Cinder concrete in cement 1:15 (1 cement: 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications - Third Floor	Cum	6.00	2361.00	Rupees Two Thousand Three Hundred Sixty One Only
150	Providing INTEGRAL CRYSTALINE Waterproofing treatment to the sunken portion of toilets. Using Crystalline Slurry of approved make @ 1.40 kg per SQM in two coats (0.7 Kg per coat) confirming to ASTM S 1202 & DINV 18998 standards.	Sqm	92.00	596.00	Rupees Five Hundred Ninety Six Only
151	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids,cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all complete as per the specification	Sqm	525.00	732.00	Rupees Seven Hundred Thirty Two Only
152	Providing TEAK WOOD frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications	Cum	0.30	230805.00	Rupees Two Lakh Thirty Thousand Eight Hundred Five Only
153	Providing White Sal Wood frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications - Ground Floor	Cum	0.20	79355.00	Rupees Seventy Nine Thousand Three Hundred Fifty Five Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
154	Providing White Sal Wood frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications - First Floor	Cum	0.19	79355.00	Rupees Seventy Nine Thousand Three Hundred Fifty Five Only
	Above 125%	Cum	0.01	75167.92	Rupees Seventy Five Thousand One Hundred Sixty Seven and Ninety Two Paise Only
155	Providing White Sal Wood frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications - Second Floor	Cum	0.19	79355.00	Rupees Seventy Nine Thousand Three Hundred Fifty Five Only
	Above 125%	Cum	0.01	75167.92	Rupees Seventy Five Thousand One Hundred Sixty Seven and Ninety Two Paise Only
156	Providing White Sal Wood frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications - Third Floor	Cum	0.19	79355.00	Rupees Seventy Nine Thousand Three Hundred Fifty Five Only
	Above 125%	Cum	0.01	75167.92	Rupees Seventy Five Thousand One Hundred Sixty Seven and Ninety Two Paise Only
157	KSRB 9.5-1 : Providing and fixing in position fully panelled Teak wood shutters for doors, with styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawingand panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34	Sqm	6.00	10304.00	Rupees Ten Thousand Three Hundred Four Only
	Above 125%	Sqm	8.40	8809.40	Rupees Eight Thousand Eight Hundred Nine and Forty Paise Only
158	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all-round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part-I) 1991. From manufacturer (Factory) complete as per specification. Ground Floor	Sqm	6.00	3809.00	Rupees Three Thousand Eight Hundred Nine Only
159	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all-round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part-I) 1991. From manufacturer (Factory) complete as per specification. First Floor	Sqm	6.00	3809.00	Rupees Three Thousand Eight Hundred Nine Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
160	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all-round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part-I) 1991. From manufacturer (Factory) complete as per specification. Second Floor	Sqm	6.00	3809.00	Rupees Three Thousand Eight Hundred Nine Only
161	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all-round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part-I) 1991. From manufacturer (Factory) complete as per specification. Third Floor	Sqm	6.00	3809.00	Rupees Three Thousand Eight Hundred Nine Only
162	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws,raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - Ground Floor	Sqm	74.00	7697.00	Rupees Seven Thousand Six Hundred Ninety Seven Only
163	KSRB 7.11 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws,raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - First Floor	Sqm	33.00	7703.00	Rupees Seven Thousand Seven Hundred Three Only

Contractor

Executive Engineer(P

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
164	KSRB 7.11 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws,raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - Second Floor	Sqm	33.00	7709.00	Rupees Seven Thousand Seven Hundred Nine Only
165	KSRB 7.11 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws,raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - Third Floor	Sqm	33.00	7716.00	Rupees Seven Thousand Seven Hundred Sixteen Only
167	Providing and fixing M.S.grill work for windows and ventilators weighing 21 kg/sqm using M.S. flats, or M.S.square rods, or combination of M.S.flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifictions. Specification No. KBS 7.12 (Considered 18 Kg/sqm)	Kgs	3438.00	103.00	Rupees One Hundred Three Only
168	Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. Ground Floor	Sqm	22.10	5007.00	Rupees Five Thousand Seven Only

Contractor

Executive Engineer

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
169	Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications.	Sqm	64.00	3552.00	Rupees Three Thousand Five Hundred Fifty Two Only
170	Providing and fixing 65mmx90mm GRP Doorframe fabricatedusing E-Glass Chopped Strand Mat (CSM). U.V-stabilizedIsopthalic Gelcoat and Isopthalic resin. The thickness of the GRPskin shall not be less than 2.0 mm. The doorframe consists of foursegmens, which are providedwithplug-in-socket arrangementin-situ in the mould. The segments are plugged in and are joinedtogether by means of screws. The GRP frame shall be providedwith wooden reinforcement of 6 locations fro high screw holdingcapacity for fixing metallic hold fast and shall be consolidated byfilling with medium density foam/Plaster with fibre reinforcement.Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat holdfast shall be provided with the frame - Ground Floor	Rmtr	28.50	596.00	Rupees Five Hundred Ninety Six Only
171	Providing and fixing 65mmx90mm GRP Doorframe fabricatedusing E-Glass Chopped Strand Mat (CSM). U.V-stabilizedIsopthalic Gelcoat and Isopthalic resin. The thickness of the GRPskin shall not be less than 2.0 mm. The doorframe consists of foursegmens, which are providedwithplug-in-socket arrangementin-situ in the mould. The segments are plugged in and are joinedtogether by means of screws. The GRP frame shall be providedwith wooden reinforcement of 6 locations fro high screw holdingcapacity for fixing metallic hold fast and shall be consolidated byfilling with medium density foam/Plaster with fibre reinforcement.Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat holdfast shall be provided with the frame - First Floor	Rmtr	28.50	602.00	Rupees Six Hundred Two Only
172	Providing and fixing 65mmx90mm GRP Doorframe fabricatedusing E-Glass Chopped Strand Mat (CSM). U.V-stabilizedIsopthalic Gelcoat and Isopthalic resin. The thickness of the GRPskin shall not be less than 2.0 mm. The doorframe consists of foursegmens, which are providedwithplug-in-socket arrangementin-situ in the mould. The segments are plugged in and are joinedtogether by means of screws. The GRP frame shall be providedwith wooden reinforcement of 6 locations fro high screw holdingcapacity for fixing metallic hold fast and shall be consolidated byfilling with medium density foam/Plaster with fibre reinforcement.Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat holdfast shall be provided with the frame - Second Floor	Rmtr	28.50	608.00	Rupees Six Hundred Eight Only

Contr

Executive Engineer

Scanned with CamScanner

1	Description of Item	Unit	Qty	Rate in	
				Figures	Words
	2	3	4	5	6
173	Providing and fixing 65mmx90mm GRP Doorframe fabricatedusing E-Glass Chopped Strand Mat (CSM). U.V-stabilizedIsopthalic Gelcoat and Isopthalic resin. The thickness of the GRPskin shall not be less than 2.0 mm. The doorframe consists of foursegmens, which are providedwithplug-in-socket arrangementin-situ in the mould. The segments are plugged in and are joinedtogether by means of screws. The GRP frame shall be providedwith wooden reinforcement of 6 locations fro high screw holdingcapacity for fixing metallic hold fast and shall be consolidated byfilling with medium density foam/Plaster with fibre reinforcement.Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat holdfast shall be provided with the frame - Third Floor	Rmtr	28.50	615.00	Rupees Six Hundred Fifteen Only
174	Providing and fixing factory made single leaft rigid GRP Sandwich composite door shutter of 32mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and on layer of 45 gsm E-Glass Chopped strand Mat (CSM), impregnated with orthopthalic polyster resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 29mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not less than 28mmx32mm and also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc, shall be provided. A structural - Ground Floor	Sqm	7.90	3973.00	Rupees Three Thousand Nine Hundred Seventy Three Only
175	Providing and fixing factory made single leaft rigid GRP Sandwich composite door shutter of 32mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and on layer of 45 gsm E-Glass Chopped strand Mat (CSM), impregnated with orthopthalic polyster resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 29mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not less than 28mmx32mm and also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc, shall be provided. A structural - First Floor	Sqm	7.90	3979.00	Rupees Three Thousand Nine Hundred Seventy Nine Only
76	Providing and fixing factory made single leaft rigid GRP Sandwich composite door shutter of 32mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and on layer of 45 gsm E-Glass Chopped strand Mat (CSM), impregnated with orthopthalic polyster resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 29mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not less than 28mmx32mm and also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc, shall be provided. A structural - Second Floor	Sqm	7.90	3985.00	Rupees Three Thousand Nine Hundred Eighty Five Only

actor

Executive Engineer(P)

Scanned with CamScanner

NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
177	Providing and fixing factory made single leaft rigid GRP Sandwich composite door shutter of 32mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and on layer of 45 gsm E-Glass Chopped strand Mat (CSM), impregnated with orthopthalic polyster resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 29mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not less than 28mmx32mm and also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc, shall be provided. A structural - Third Floor	Sqm	7.90	3991.00	Rupees Three Thousand Nine Hundred Ninety One Only
178	Providing and fixing 1mm thick M.S. sheet garage door with frame and diagonal braces of size 40x40x6 mm angle Iron, 3.15mm thickM.S. Gusset plates at the junctions and corners, with handles, stoppers and locking arrangements etc., including applying a priming coat of redlead paint cost of materials, labour, HOM of machinery complete as perspecifications. Double leaf door of size 2.4x2.4m	Sqm	4.20	2920.00	Rupees Two Thousand Nine Hundred Twenty Only
179	Fixing of door frame in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications - Ground floor	Nos	4.00	1308.00	Rupees One Thousand Three Hundred Eight Only
180	Fixing of door frame in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications - First floor	Nos	2.50	1312.00	Rupees One Thousand Three Hundred Twelve Only
	Above 125%	Nos	0.50	1699.56	Rupees One Thousand Six Hundred Ninety Nine and Fifty Six Paise Only
181	Fixing of door frame in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications - Second floor	Nos	2.50	1316.00	Rupees One Thousand Three Hundred Sixteen Only
	Above 125%	Nos	0.50	1703.28	Rupees One Thousand Seven Hundred Three and Twenty Eight Paise Only

Contractor

Scanned with CamScanner

NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
182	Fixing of door frame in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications - Third floor	Nos	2.50	1320.00	Rupees One Thousand Three Hundred Twenty Only
	Above 125%	Nos	0.50	1707.01	Rupees One Thousand Seven Hundred Seven and One Paise Only
183	Fixtures-Providing and fixing fixtures for Door incluidng screws etc., complete as per specification and as per the directions by the Engineer in charge For Chromium plated Brass butt hinges (heavy) type 75x65x4 mm weighing not less than 200gms	Nos	26.25	115.00	Rupees One Hundred Fifteen Only
	Above 125%	Nos	3.75	115.00	Rupees One Hundred Fifteen Only
184	Chromium plated Brass handles 125 mm with plate 175 x32 mm	Nos	10.00	201.00	Rupees Two Hundred One Only
185	Chromium plated Brass mortice latch and lock 100x65 mm with 6 levers and a pair of brass lever handles	Nos	2.00	569.00	Rupees Five Hundred Sixty Nine Only
186	Brass tower bolt (barrel type) 250x10 mm	Nos	20.00	287.00	Rupees Two Hundred Eighty Seven Only
187	Brass tower bolt (barrel type) 150x10 mm	Nos	10.00	172.00	Rupees One Hundred Seventy Two Only
188	Chromium plated Brass screws 20 mm	Nos	180.00	2.00	Rupees Two Only
189	Hydraulic door clouser - aluminium body	Nos	9.00	1517.00	Rupees One Thousand Five Hundred Seventeen Only
190	Brass 150 mm floor door stopper weighing not less than 0.357kg	Nos	5.00	195.00	Rupees One Hundred Ninety Five Only
	Above 125%	Nos	4.00	195.00	Rupees One Hundred Ninety Five Only
191	Providing and fixing Stainless steel 304 Grade for staircase railing, Balconys Ramps with hand rails 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges etc., complete as per specification	Sqm	75.80	7631.00	Rupees Seven Thousand Six Hundred Thirty One Only
192	Providing and fixing of Aluminium composite panel of approved make and colour for wall cladding for straight Brick/Rcc/stone walls & coloumns/beams with necessary aluminium frame works at required level made out of 50x25x3mm C section or equalent. The panel should consist of 2.5 mm thermoplastic core of antitoxic LDPE sandwiched between 0.25 skins thick aluminium sheet making a total panel thickness of 3mm. The surfaces will be finished with PVDF based coating on topsides and service coating on reverse sides would be in polyester paint. The system shall be fixed using GI brackets, aluminium L cleats and stainless steel bolts and nuts complete with spring washer and cap nuts and all other necessary accessories, sealing shall be done using weather sealant of Dow Corning 789 with necessary rods etc., complete	Sqm	60.00	5608.00	Rupees Five Thousand Six Hundred Eight Only

Contractor

Executive Engineer(P

Scanned with CamScanner

1	Description of Item	Unit	Qty	Rate in	
				Figures	Words
	2	3	4	5	6
193	Providing,fabricating and fixing of stick type structural glazing using alluminium extrusions of 63.5mmx58.00mmx2.25mm of 1.73 kgs/mtr for vertical and horizantal members and 63.5mmx38.1x1.33mm of 0.759kg/mtr, as outer franme with electro anodized paint coated block finishing,using 6mm thick imported glass reflective hard coated ocean blue raw glass with allneccessary accssories like ultra glass silicon sealent of space tape,masking tape ,galvanized anchaor bolt, machine screws,6mm thick M.S.angle 50mmx150mmx6mm M.S.galvanized L Brackets, structural sealent setting clocks, fasteners,wall connection etc., complete.	Sqm	189.00	7295.00	Rupees Seven Thousand Two Hundred Ninety Five Only
194	Providing and fixing M.S. Grill over existing compound wall as per using 16mm x 16mm M.S. Square rod at 150mm c/c spacing and 6mm x 40mm M.S. flats at horizontal and 6mm x12mm M.S. flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding wherever necessary. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per specification	Sqm	80.00	6485.00	Rupees Six Thousand Four Hundred Eighty Five Only
195	Providing, fabricating and fixing partition frame work consisting of 50mm x 50mm sal wood frame work at spacing not exceeding 600mm c/c fixed to the bottom and ceiling, the partition shall be skinned on both sides using 12mm thick commercial plywood of approved brand termite and water resistance, and top covered with 4mm thick approved quality veneer finished with melamine polish, complete including cost and conveyance of all materials, labour for all items of work, HOM of equipment as per specification.	Sqm	13.86	10180.00	Rupees Ten Thousand One Hundred Eighty Only
196	Providing, fabricating, assembling and fixing in position aluminium partitions using sections in combination of plain, single grove and double grove as per requirements for the frames of overall size 101.6mm x 44.45mm, 3.18mm.thick having section weight, plain sections 2.40kg/m single grove section 2.541kg/m. and double grove section 2.683 kg/m and bottom bottom member 114.3 mm x 44.45 mm 3.18 mm thick and 2.6 46 kg/m; aluminium louvres of size 77.6mmx27.6mm 1.7mm. thick section weight 0.483kg/m; bottom portions provided with 12mm. thick pre laminated sheet both side of approved colour lamination exterior grade; aluminium sections of mat finish or glossy finish using section, spacing of vertical member shall not exceed 0.6 m. c to c; sections are cut to the required lengths, joints mitered and corners grinded subdividing frames tennoned and riveted to the frames, the assembled frame should be stiffened with corner angles stripped and fixed with screws, rawl plugs and teak wood gutties to R.C.C.columns or masonry on sides, R.C.C. lintels or beams at top and floor at bottom, including cutting chistling and making good with cement mortar to match the surface, providing and fixing bottom panel filled with the materials to a height of 0.9m. from floor level; and 5.5mm. thick plain glass for middle portion viz., 0.9m. to 2.13 m. and top panel with lower sections, the glass and panels fitted with glazing clips of 19mmx17.3mm. with thickness of 0.9mm. weight 0.124kg/m; aluminium sections pre-treated for removal of any rust and prevention of further rust formation, and coated with greasy materials for non-adherence of mortars or any other sticky materials; vertical members embedded in the flooring by making suitable size holes and fixing with cement mortar, with necessary opening for fixing of doors of standard size (excluding cost of door opening) All the frame should be throughly cleaned free from rust, scale or dirt including cost of materials, fixtures, labour and HOM of machinery complete as per specifications	Sqm	131.70	5873.00	Rupees Five Thousand Eight Hundred Seventy Three Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
197	KSRB 7.17 : Providing, fabricating, assembling and fixing in position aluminium doors using following aluminium mat finish or glossy finish, outer frame plain section 101.6x44.45mm thickness 3.18mm, section weight 2.404 kg/m, door shutters vertical section 44.62x44.45mm thickness 3.18mm, section weight 1.505kg/m, top section 47.62x44.45mm thickness 3.00mm, section weight 1.426kg/m bottom section 114.3x44.45 thickness 3.18mm, section weight 2.646kg/m, door central section 49.91x44.45mm thickness 3.00mm, section weight 1.495 kg/m glazing clips 19x17.3x11mm thickness 0.9mm section weight 0.124kg/m; aluminium sections cut to length joint metred corners grinded, the shutters pivoted opening arrangement with heavy duty aluminium alloy automatic door closures floor mounted, providing and fixing standard approved accessories, such as aluminium handle for full width or length, tower bolts, lock, pivots: P.V.C. or rubber gasket with 5.5m. thick plain glass for top and bottom panel; aluminium sections treated for removal of any rust and prevention of further rust formation, and coated with greasy materials for non-adherance of mortars or any other sticky materials; the assembled frame fitted with the corner angles, strips and fitted with screws, rawl plugs or teakwood gutties to R.C.C. columns or masonry on sides. beams and flooring in bottom. including cutting, chistling and making good with cement mortar to match the surface; all the frames throughly cleaned free from rust, scale, or dirt including cost of materials, fixtures,. -do- using aluminium section powdered coated to a minimum of 60-70 microns with exterior durable pure polyester grade powder of approved quality.	Sqm	6.30	7834.00	Rupees Seven Thousand Eight Hundred Thirty Four Only
198	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet. Point wirig using class A Materials a) Short point upto 3.0M from tapping point to outlet via switch box	Each	125.00	166.00	Rupees One Hundred Sixty Six Only
199	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet. Point wirig using class A Materials b) Medium point above 3.0M upto 6.0M from tapping point to outlet via switch box	Each	175.00	247.00	Rupees Two Hundred Forty Seven Only
200	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet. Point wirig using class A Materials c) Long point above 6.0M upto 10.0M from tapping point to outlet via switch box	Each	125.00	384.00	Rupees Three Hundred Eighty Four Only
201	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet. Point wirig using class A Materials d) Two outlet in a row, above 3.0M upto 6.0M from tapping point to outlet via switch box	Each	18.75	486.00	Rupees Four Hundred Eighty Six Only
	Above 125%	Each	6.25	546.01	Rupees Five Hundred Forty Six and One Paise Only

Contractor

BESCOM.

Executive Engineer(

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
202	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet. Point wirig using class A Materials e) Three outlet in a row, above 6.0M upto 10.0M from tapping point to outlet via switch box	Each	5.00	682.00	Rupees Six Hundred Eighty Two Only
203	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.Cwall - 1-3Way	Each	30.00	105.00	Rupees One Hundred Five Only
204	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.Cwall - 6 Way	Each	17.50	139.00	Rupees One Hundred Thirty Nine Only
	Above 125%	Each	7.50	143.69	Rupees One Hundred Forty Three and Sixty Nine Paise Only
205	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.Cwall - 8Way	Each	25.00	161.00	Rupees One Hundred Sixty One Only
206	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.Cwall - 10-12Way	Each	45.00	183.00	Rupees One Hundred Eighty Three Only
	Above 125%	Each	5.00	189.67	Rupees One Hundred Eighty Nine and Sixty Seven Paise Only
207	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box - a)1-3Module	Each	30.00	125.00	Rupees One Hundred Twenty Five Only
208	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box - b)6 Module	Each	17.50	199.00	Rupees One Hundred Ninety Nine Only
	Above 125%	Each	7.50	201.16	Rupees Two Hundred One and Sixteen Paise Only
209	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box - c)8 Module	Each	25.00	230.00	Rupees Two Hundred Thirty Only
210	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box - d) 10Module	Each	25.00	261.00	Rupees Two Hundred Sixty One Only
211	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box - e) 12Module	Each	20.00	307.00	Rupees Three Hundred Seven Only
	Above 125%	Each	5.00	264.39	Rupees Two Hundred Sixty Four and Thirty Nine Paise Only
212	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 - a) 6Amps one Way	Each	125.00	72.00	Rupees Seventy Two Only

Contractor

Executive Engineer(P)

Scanned with CamScanner